3. Front Axle


A: REMOVAL

- 1) Lift up the vehicle, and then remove the front wheels.
- 2) Remove the nut axle.

CAUTION:

Do not loosen the nut - axle while the front axle is loaded. Doing so may damage the hub unit COMPL.

- (1) Lift the crimped section of the nut axle.
- (2) Remove the nut axle using a socket wrench while depressing the brake pedal.



- 3) Remove the disc brake assembly. <Ref. to BR-25, REMOVAL, Front Disc Brake Assembly.>
- 4) Remove the disc rotor. <Ref. to BR-22, REMOVAL, Front Disc Rotor.>


- 5) Disconnect the tie-rod end.
 - (1) Pull out the cotter pin (a).
 - (2) Remove the castle nut (b).
 - (3) Using a tie-rod ball joint puller, remove the tie-rod end (c).

CAUTION:


Be careful not to damage the boot of the joint.

Preparation tool:

Tie-rod ball joint puller




6) Remove the bolts, and remove the front ABS wheel speed sensor.



7) Remove the stabilizer link and ball joint.

CAUTION:


Be careful not to damage the boot of the joint.



- 8) Remove the front drive shaft. <Ref. to DS-48, REMOVAL, Front Drive Shaft.>
- 9) Remove the housing assembly front axle.

CAUTION:

- Be careful of the weight of the housing assembly front axle.
- Be careful not to damage the spline portion of the drive shaft.
 - (1) Place an alignment mark (a) on the adjusting bolt and the strut assembly.
 - (2) Remove the adjusting bolts and flange bolts for the strut assembly, and then remove the housing assembly front axle.



NOTE:

While holding the adjusting bolt side, tighten the nut side.

10) For removal of the hub unit COMPL - front axle, refer to "Front Hub Unit Bearing". <Ref. to DS-25, RE-MOVAL, Front Hub Unit Bearing.>

B: INSTALLATION

- 1) Install the housing assembly front axle to the strut assembly.
 - (1) Align alignment marks on the camber adjusting bolt and strut.
 - (2) While holding the bolt head of adjusting bolt, tighten the nut.


Tightening torque:

155 N·m (15.8 kgf-m, 114.3 ft-lb)

- 2) Install the front drive shaft assembly. <Ref. to DS-49, INSTALLATION, Front Drive Shaft.>
- 3) Install the ball joint assembly.

CAUTION:

- Before tightening, make sure the bottom surface of the housing assembly front axle and the stepped section of ball joint are in contact.
- · Be careful not to damage the boot of the joint.



- (a) Bottom surface of housing ASSY front axle
- (c) Housing ASSY front axle
- (d) Ball joint ASSY

(b) Raised section of ball joint

Tightening torque:

50 N·m (5.1 kgf-m, 36.9 ft-lb)

4) Install the front ABS wheel speed sensor.

Tightening torque:

7.5 N·m (0.8 kgf-m, 5.5 ft-lb)

- 5) Install the disc rotor.
- 6) Install the disc brake assembly.

Tightening torque:

STI model: 155 N·m (15.8 kgf-m, 114.3 ft-lb)

Except for STI model: 80 N·m (8.2 kgf-m, 59.0 ft-lb)

7) Install the brake hose bracket.

Tightening torque:

33 N·m (3.4 kgf-m, 24.3 ft-lb)

8) Install the stabilizer link assembly.

Tightening torque:

60 N·m (6.1 kgf-m, 44.3 ft-lb)

- 9) Connect the tie-rod ends.
 - (1) Connect the tie-rod ends to the housing assembly front axle.
 - (2) Tighten the castle nuts to the specified torque.


CAUTION:

When connecting the tie-rod, do not hit the cap at bottom of tie-rod end with a hammer.

Tightening torque:

27 N·m (2.8 kgf-m, 19.9 ft-lb)

- (3) Tighten the castle nut within the range of 60° so that the cotter pin hole and cutout portion of the castle nut are aligned.
- (4) Insert the cotter pin, and bend the tip of the pin to fix it.



10) While depressing the brake pedal, tighten the nut - axle to the specified torque.


CAUTION:

Do not load the front axle before tightening the nut - axle. Doing so may damage the hub unit COMPL.

Tightening torque:


220 N·m (22.4 kgf-m, 162.3 ft-lb)

11) Inspect the lean of axis direction using a dial gauge. Replace the hub unit COMPL - front axle if the play exceeds the limit.



Service limit:

Maximum: 0.05 mm (0.0020 in)
12) After tightening the nut - axle, lock it securely.




13) Install the front wheels, and perform the following inspections.

Tightening torque:

120 N·m (12.2 kgf-m, 88.5 ft-lb)

- 1. Check the wheels for smooth rotation.
- 2. Check that there is no play by moving the upper and lower portions of front tire in an axial direction with the brake pedal released.



- Play exists → Check the hub unit COMPL front axle. <Ref. to DS-31, INSPECTION, Front Hub Unit Bearing.>
- 3. Check that there is no play by moving the upper and lower portions of front tire in an axial direction with the brake pedal depressed.
- Play exists → Replace the ball joint assembly. <Ref. to FS-33, REMOVAL, Front Ball Joint.>
 14) Inspect the wheel alignment and adjust if necessary.
- Inspection: <Ref. to FS-10, INSPECTION, Wheel Alignment.>
- Adjustment: <Ref. to FS-15. ADJUSTMENT. Wheel Alianment.>

CAUTION:

When the wheel alignment has been adjusted, perform "VDC sensor midpoint setting mode". <Ref. to VDC-16, ADJUSTMENT, VDC Control Module and Hydraulic Control Unit (VDCCM&H/U).>

15) Perform reinitialization of the auto headlight beam leveler system. (Model with auto headlight beam leveler) <Ref. to LI-16, PROCEDURE, Auto Headlight Beam Leveler System.>